



EXPLANATION	
	Portland Cement Grout
	Bentonite Grout (≥30% solids)
	Gravel (1/8 x 1/4 in.) / Granular Bentonite (8 Mesh) (~2:1 by weight)
	Gravel Pack (1/8 x 1/4 in. silica gravel)
	Well Screen: 0.050 in. louvered slots

Nye County, Nevada Nuclear Waste Repository Project Office	
Groundwater Evaluation Drilling Program NC-GWE-GF-3T Well Completion Diagram	
Date: 05/14	Checked by: LK
Scale: none	Drawn by: JSW

Note: All depths referenced to below original ground level datum